



Note:
 1. Dimensions and levels in drawings are in meters, levels are based on local seal level.
 2. 6 pedestals for caisson predredation shall be provided in single line with plan dimensions 35x20m each. Total length of pedestals shall be 50m, length of inclined frame vehicle towing area shall be 5m, and total length of ramp slipway shall be 90.0m.
 3. 2x50t gantry cranes and 1x250t tower crane shall be provided at predredation yard with rail length 200m each. 2 gantry cranes will share 1 rail.

Tianjin Port Engineering Design and Consulting Ltd of China Communication Construction Company			
Principal of Project	Date	Project Name	Project No. CPT-06-110
Approved By	Date	Site Status (in accordance with the current status)	Submission No.
Chief Designer	Date	Project Subjects	Phase
Checked By	Date		Scale
Corrected By	Date	Drawing Name	1:700
Designed By	Date	Master Plan	
Plotted By	Date		Drawing No. TPC-01